



Project Planning and Implementation of Vegetation Management Practices during Development, Permitting, Construction, and Operations of Solar Projects


William Risse- Senior Permitting Specialist- National Grid Renewables



Planning



Implementation/ Construction



Operations



Planning and Development of Solar Projects

Integrating Vegetation Management Planning into the Development
Process

Planning for Success

What makes a good solar site?

- Point of Interconnection and Upgrade Costs
- Quality Solar Resource
- Willing Landowners
- Generally Suitable Land (Ideally Flat, Ideally Minimal Environmental Constraints)




Planning and Development



What We Know for Permit Submittal

- Site/Land Control
- Existing Conditions (Typically Ag Use)
- Soils
- Wetlands
- Hydrology
- Preliminary Design, Preliminary Transmission Route
- Anticipated Environmental Impacts
- Best Management Practices
- Suitable Seed Mixes for the Above



What We Don't Know

- **Will the Project be Approved as Proposed**
- **Final Civil Layout**
- **Contractor To Carry Plan Forward**
- **Operations Manager and Operations Contractor**




An Ideal VMP- Developers Perspective

- **Goals**
- **Array Best Practices, Strategies, and Options for the Site**
- **Seed Mixes**
 - Implementation. Avoidance of highly specific techniques (ie plugs, detailed soil surveys)- looking for more general seed mixes suitable for an array of conditions, establish quickly to reduce erosion, improve long term management and viability and can still provide pollinator benefits.
 - Increasing focus on low growth option under array, challenges in diversity.
- **A Final Civil Layout Doesn't Have Large Impacts on Vegetation Management Practices**
 - The final layout will identify a more refined area for the practices to be carried out within.
- **Clear VMP Approval Process**
 - Who reviews, who approves, who aggregates and resolves conflicting comments/perspectives, and on what timeline?
- **Flexibility to Implement a New Plan in the Future**
 - For example, what if a grazing partner approaches a Project at year 5?

Late-Stage Development


Successfully Passing the Solar Baton to the Engineering Procurement and Construction Team

- Flexibility in Final Design- Value Added Engineering and Tech Improvements
- Final Approved Documents To Carry into Construction Contract
 - VMP
 - AIMP
 - Archaeological Concurrence
 - Wetland Concurrence



An Ideal VMP for an EPC Bid

- Contractors bidding into an RFP to Engineer, Procure, and Construct (EPC) a multi-thousand (community solar) or multi-million (utility scale) project are looking for a hard and fast set of rules that they can apply to provide an apples to apples (and competitive bid) for Utility Scale Project.
- Making a \$500k assumption regarding vegetation management, fencing, other factors could tip the scales in favor of another company's bid.
- Developers are looking for as near a “final” approved VMP and other such plans prior to the conclusion of the site permit (state or local) process as possible to best inform potential EPC bidders of their commitments.
- Uncertainty following contract execution leads to change orders (CO) and budgeting headaches for contractor and owner.
- Financial modelling and Power Purchase Agreement obligations.



Say NO to the CO

Construction of Solar Projects

Integrating Vegetation Management into the Construction Process

Typical Project Components

- Inverters
- Modules/Panels
- Racking
- Gravel Access Roads
- Electrical Components (e.g. cables, transformers, control systems and Point of Interconnection)
- Security Fencing and Screening
- Storm-water Retention Areas
- Operation and Maintenance Shed



Sunrise Community Solar

Best Management Practices



Site Preparation



Delphinus Community Solar



Yellowbud Solar Project

Access Roads



Pier Installation



DodgeSun Community Solar



Rosemount Community Solar

Soil Decompaction



Racking




Deneb Community Solar



Chisago Community Solar

Modules / Panels



Bifacial Panel

Thin Film



Polycrystalline



Inverters



Underground Collection



Point of Interconnection- Substations



Restoration and Re-Vegetation



Koppelman Community Solar



Solar Project Components – Restoration



St. John's Solar



Kramer Solar

Operations of Solar Projects

Ongoing Vegetation Management Strategies

Considerations in Management

- **Nimble and flexible VMPS and operational requirements allow for new creative approaches.**
 - Noxious Weed Management, Woody Vegetation Management.
 - Spot Seeding
 - Mowing Schedule
 - Expedient SWPPP Closeout A Challenge With Diverse Plantings and Their Establishment Timeframes
- **Monitoring and Reporting.**
- **Our current Minnesota strategy is primarily mowing, but we are exploring grazing opportunities.**
- **National Grid Renewables is not currently seriously considering haying in Minnesota due to state statute.**





William Risse

Senior Permitting Specialist

wrisse@nationalgridrenewables.com

Phone 952-300-9476